



Installations over Radiant Heated Floors

Avion Commercial Flooring – Creek Street, Boardwalk, Mill Street, Boulevard and Avenue may be installed over radiant heated floors, provided the operating temperature does not exceed 85°F / 29°C.

Note: During installation, lower the radiant heated floor temperature to a minimum 65°F / 18.3°C. This temperature should be maintained for at least 24 hours before and during and 48 hours after completion of the installation. On ground floors, the radiant heating system should have a proper moisture barrier beneath it. The concrete should be tested for moisture before the LVT flooring is laid. Heating pipes must be at least 2” or 50 mm below the floor surface. If the heating pipes are too close to the vinyl flooring, the vinyl may discolor next to the pipe work.

Gradually increase temperature in increments of 5° per hour. Please check with your Adhesive Manufactures for the appropriate adhesive recommended in this installation application.

Meridian Flooring Products

2732 Highway 74 West

Wadesboro, NC 28170

customerservice@meridianfloor.com